

## **SCOPE OF WORKS**

**FEA Site:** FEA Namaka Site, Nadi.

### **1. Fencing works for zone indicated in drawing**

FEA Requirements / recommendations:

1. Install footing into soft stone base + 2 row block wall
2. Additional 3 row block above ground
3. Trimdeck 2100 cladding on c-channel
4. 150mm block wall column at the ends at 15m centers
5. 50mm GWI Grade C Existing fence posts with PVC capping at 300 centers. ( if required extend to required 3m height above ground level. 3 Rows of barbed wire.

### **Notes:**

Contractor must do a temporary fence during these works – HV zone (Safety of Public)

Contractor to submit their design/drawings and options for the fencing works.

Contractor must ensure engineers certificate will be provided for the fencing works.