

Tender MR28/2016 - CONSTRUCTION OF GABION WALL/RETAINING WALL

AT NADARIVATU SWITCHYARD

Addendum-01

Scope of Works:

3.7 FEA wishes to stabilize a slope around Transmission Tower 60-1, near the Tuvatu Gold Mine site at Sabeto, Lautoka. Remove existing damaged rock wall, and all loose soil. Construct a gabion wall, concept is similar as to the one at Nadarivatu Switchyard, but a vertical arrangement of the wall will be required. Suitable granular fill material, free of silt and organics shall be used as backfill. Backfill shall be placed in 300mm layers and compacted.



*Sketch of the Area and Wall Arrangement.*

Wall dimensions are 10m length, 3m height, 1m wide, embedded 300mm into in-situ soil.

3.8 Approximately 150m of drain clearance works is associated with 3.7 above.

3.9 A site meeting has been arranged at 9.30am on Friday 1 April 2016. Contractors are to be assembled at the roadside near Fulton College, Sabeto, from where FEA will guide you to the tower site. Please call Anees on 9999613 in case you are not able to locate the site.