

TENDER NO - MR 133 /2016

PROJECT: SUPPLY TO NADI LAND DEVELOPMENT, NADI

SCHEME: G46-16B

Notes:

- 1. <u>Bidders to submit copies of FEA training records with current validity. Bids without</u> this will be disqualified.
- 2. Safety Plan to be included in tender bid.
- 3. Safety Report for 2015, 2016 to be submitted with tender.
- 4. List of Construction projects completed for FEA to be submitted with tender.
- 5. Please pay specific attention to Clause 12 under PART C, Contractor Requirements: "Electric Power Lineman/ Line Mechanic/ Line Worker Contractor shall ensure that the Construction Team comprises a minimum of five personnel, at least one of whom shall be a certified Electric Power Lineman/ Line Mechanic/ Line Worker. The remaining team members shall comprise of registered Trainee Line Workers/ Trainee Linemen/ Trainee Line Mechanic working on the project on a full time basis. Records of these personnel shall be submitted with the bid.
 - Contractors unable to submit positive proof (Certificates) that they meet this key requirement shall not be considered.
- 6. Please pay specific attention to Clause 24 under PART C, Contractor Requirements: "Transportation of material The Contractor shall transport all materials from the FEA Depot (exact depot dependent on project location) to worksite, EXCEPT concrete poles, which may be picked up from Humes Depot, or otherwise as specified by FEA."



All work requiring FEA supervision shall be started and completed during normal working hours. Any supervision work required after normal working hours, cost will be Contractors responsibility.

FIRST SCHEDULE

A: SPECIAL CONDITIONS OF CONTRACT -

1. The works shall comprise the installation of power lines as per attached Drawing No. A2-04- N54-352

Please enter unit rates and lump-sum prices in table below.	
The total Contract sum for the works shall be \$	VIP.

Power Line Construction SCHEME NO: G46-16B Line Construction for Supply to Nadi Land Development, Nadi				
Description	Quantity	Unit Rate	Total	
Install concrete power pole [10.2m]	11			
Install concrete power pole [11m]	1			
Install 13B dressing	1			
Install 11B dressing	5			
Install 5B dressing	1			
Install 3B dressing	1			
Install 1Bdressing	9			
Install N/O LV Link	1			
Install 300kVA pole mount transformer	1			
Install 3 Ø HV Wasp conductor (route length-km)	192m			
Install 3Ø LV Wasp conductor (route length - km)	2104m			
LUMP SUM COSTS:				
o. Material Transport Cost	Total			
Transportation of materials from FEA Depot/Supplier to site				
	E NO: G46-16B Line Construction for Supply to Nadi Land Develor RATES: Description Install concrete power pole [10.2m] Install concrete power pole [11m] Install 13B dressing Install 11B dressing Install 5B dressing Install 3B dressing Install 3B dressing Install 3B dressing Install 3B dressing Install 3 dressing Install 4 dressing Install 5 dressing In	E NO: G46-16B Line Construction for Supply to Nadi Land Development, Nadi RATES: Description Quantity Install concrete power pole [10.2m] 11 Install concrete power pole [11m] 1 Install 13B dressing 1 Install 11B dressing 5 Install 5B dressing 1 Install 3B dressing 1 Install 3B dressing 1 Install 1Bdressing 1 Install 1Bdressing 1 Install 3B dressing 1 Install 3B dressing 1 Install 3B dressing 1 Install 3D Hy Usink 1 Install 3 Ø Hy Wasp conductor (route length-km) 192m Install 3 Ø LV Wasp conductor (route length-km) 2104m SUM COSTS: D. Material Transport Cost Total	E NO: G46-16B Line Construction for Supply to Nadi Land Development, Nadi RATES: Description Quantity Rate Install concrete power pole [10.2m] 11 Install concrete power pole [11m] 1 Install 13B dressing 1 Install 11B dressing 5 Install 5B dressing 1 Install 3B dressi	

Item No.	Vegetation Management	Total
1	Vegetation Management as required	

3. Work schedule



Latest date for commencement of the works:

7 days from issue of LPO.

(a) Date of completion of Phase 1:

1 week from issue of LPO.

(b) Date of completion of Phase 2:

2 weeks from issue of LPO.

(c) Date of completion of Phase 3:

1 weeks from issue of LPO.

(d) Date of completion of Phase 4:

1 weeks from issue of LPO.

5 weeks from issue of LPO.

- 4. For the purpose of supervising the contract on behalf of the Authority, references in the General Conditions to the Authority shall include the Unit Leader Distribution West or his designated officer. The Project Manager shall be the Unit Leader Distribution West, the Project Engineer shall be the Distribution Engineer West, and the Project Supervisor shall be the Construction Coordinator West.
- 5. Insurance (refer clause 14)

(a) Contractor's risk \$500,000.(b) Public Liability \$500,000.(c) Worker's Compensation \$250,000.

The contractor shall indemnify FEA against any claims for liability, injuries, losses, damages etc that may arise during the execution of the works.

- 6. Liquidated and ascertained damages (refer clause 20): \$200 per day.
- 7. Defects Liability period (refer clause 21): 6 months
- 8. Retention Fund (refer clause 24)

(a) Limit of retention fund: 10% of contract sum

(b) Nature of retention fund: cash

(c) Release of retention fund: Subject to no pending defect, and as per FEA

Finance Policy.

9. Tax Compliance Certificate from FRCA

FNPF Certificate

Evidence of manpower employment (eg. payroll listing, etc.)

All other relevant documents that are required as part of any tender/contract.



B: SECOND SCHEDULE

<u>Specification for Distribution Power lines for Supply to Nadi Land Development at Legalega,</u> Nadi – G46-16

1.0 General

This specification covers the installation of Distribution Power lines for Supply to Nadi Land
 Development at Legalega, Nadi as per attached Drawing No. A2- 04- N54-352 under
 conditions of Contract attached herein.

2.0 Scope of Work

Work involved in this contract is broadly classified into four phases:

- i) Transportation of materials
- ii) Installation of pole and dressing, stays etc.
- iii) Stringing of conductors
- iv) Installation of transformer, earthing, etc.

2.1 Phase One – <u>Transportation of Materials</u>

The first phase comprises of the following works:

Transportation and load of all material to the jobsite from FEA Depot, except for concrete poles which shall be picked up from Humes Depot, and spalls which shall be picked from either the FEA Depot or Humes Depot after instruction from FEA.

2.2 Phase Two – Installation of Pole and dressing, stays, etc.

This phase of the contract involves the dressing and erection of poles, the installation of stays, Isolators etc.

2.4 Phase Three – <u>Stringing of conductors</u>

This phase involves the stringing of conductors to FEA standards, their binding, sagging etc. and the digging and laying of underground cables

2.5 Phase Four – <u>Installation of Transformer</u>

This phase involves the installation of transformer, earthing, dressing etc. to FEA standards.



C: CONTRACTOR REQUIREMENTS

General Below is a list of minimum requirements for overhead power line construction contractors:

- 1) **Bid** Contractor shall submit a firm bid clearly listing unit costs for all items required. Vegetation clearing and Transportation costs shall be submitted as a lump sum.
- 2) **Site Visit** Contractor shall participate in a site visit (date, time and location as advised by FEA) which is compulsory. Bids from companies who do not participate in the site visit shall be disqualified. Site visits outside the date/time/location specified by FEA will not be entertained.
- 3) Standards All construction work shall be in compliance with FEA Standard Overhead Line Design & Construction Manual. If any instances occur whereby the requirements of this Manual cannot be complied with or where it is desired for a specific reason to depart from them, written permission must first be obtained from the FEA Unit Leader Distribution
- 4) **Materials** To ensure quality control, all material for the project shall be supplied by FEA. Non-technical items may be supplied by the contractor only if it is specifically stated in the bid document.
- 5) **Safety Record** –bid shall include a brief report on safety performance over the last two years. The report shall include all incidents and accidents.
- 6) **First Aid** each team on the jobsite must have a full First Aid Kit.
- 7) **Sub-contracting** Subcontracting shall not be permitted, except where it is specifically stated by the contractor, and only upon approval by FEA. Subcontractors shall be required to fulfil all requirements as if they were the contractor.
- 8) **Scope of works** Work involved in this contract is broadly classified into the following five phases, and progress payments shall be processed accordingly.
- 9) Transportation of material
- 10) Installation of pole and dressing, erection stays etc.
- 11) Stringing of conductors
- 12) Installation of transformer, earthing, etc.
- 13) **Contact** Contractor shall have a valid postal address, office phone/fax/e-mail contact. The Principal shall be available by mobile phone at any time.
- 14) **Work Program** Contractor shall submit a work program before start of project. This shall be part of the contract. Work shall commence within seven (7) days after receiving an official FEA Purchase Order.
- 15) **Ground condition** Contractors are to note that sub-soil comprises soapstone and could contain other services such as Telecommunication, Water & Sewerage, etc.



- 16) Electric Power Lineman/ Line Mechanic/ Line Worker Contractor shall ensure that the Construction Team comprises a minimum of five personnel, at least one of whom shall be a certified Electric Power Lineman/ Line Mechanic/ Line Worker. The remaining team members shall comprise of registered Trainee Line Workers/ Trainee Linemen/ Trainee Line Mechanic working on the project on a full time basis. Records of these personnel shall be submitted with the bid.
- 17) **Invoicing** Contractor shall submit details of work completed to allow prompt approval of invoice.
- 18) **Safety Induction** A Safety induction must be conducted before start of power line construction work.
- 19) **Instruction to Commence Work** Contractor shall NOT commence work on site unless an "Instruction to Commence Work" has been received from the Project Manager.
- 20) **Signboards** One signboard (6'X 4') must be erected at the start of the works and one at the end of the works clearly stating :

DANGER	
PROJECT:POWERLINE CONSTRUCTION – [Description of project] Driver please reduce speed. Pedestrians please use other footpath/side of road	
CONTRACTOR: Emergency phone contact: POWER LINE CONSTRUCTION WORK.	
Please reduce speed. Pedestrians please use other footpath/side of road.	
THANKS	

The above must be facing traffic entering into the work area.

The reverse face of the signage must state "Work Ends. Thank You".

- 21) **Accident Reporting** All accidents and incidents shall be reported immediately to FEA using approved forms available in the FEA Safety Plan Template, or equivalent.
- 22) **Project Updates** Contractor shall meet with FEA Project Manager, Project Engineer and Project Supervisor on a weekly basis to discuss project progress and bottlenecks. These meetings shall be minuted for records, and circulated to the appropriate stakeholders.
- 23) **Vegetation clearing** Vegetation clearing shall be in accordance with FEA Vegetation Management Policy. Vegetation, which at a mature height will exceed 2m in height, must be removed. Vegetation within falling distance from the FEA lines must be removed. Vegetation debris shall be disposed off neatly at a location agreed to by FEA. No debris shall be left by the



- roadside or blocking drains. Any debris not cleared promptly will be cleared from the site by FEA (or designated agent) at the expense of the contractor.
- 24) **Tidiness** The Contractor shall maintain the worksite in a neat and tidy condition.
- 25) **Consent for Vegetation clearing** no vegetation shall be cleared unless specific instruction to do so has been received from the Project Supervisor. Notwithstanding this, the contractor shall inform the tree owner that he is required to clear the tree, and shall obtain the owner's confirmation that he has given FEA his consent to remove the tree, prior to proceeding with cutting the tree.
- 26) Fires No fires are to be lit at jobsites for the purpose of clearing vegetation or vegetation debris.
- 27) **Village Protocols** the contractor shall comply with protocols involved in working on land owned by Indigenous Fijians to ensure smooth work progress.
- 28) **Transportation of material** The Contractor shall transport all materials from the FEA Depot (exact depot dependent on project location) to worksite, EXCEPT concrete poles, which may be picked up from Humes Depot, or otherwise as specified by FEA.
- 29) **Security** Contractor shall be responsible for the safekeeping of all materials at work site, and will be required to pay for damage and/or loss.
- 30) **Damage to property** The Contractor shall ensure that there is no damage to roadways, footpaths, drains, water-courses, properties and other services. The Contractor shall make good to the satisfaction to the owner any damage caused by the contractor.
- 31) **Portable signboards** Portable signboards must be placed as per the FEA Safety Manual along the roads, and must meet minimum FRA requirements.
- 32) **Traffic and Pedestrian Management** The Contractor shall ensure that there is minimum disruption to the flow of traffic and pedestrian. FEA procedures on Traffic Control and Pedestrian Control shall be diligently exercised. Traffic and pedestrian management shall, as a minimum, meet Fiji Roads Authority standards.
- 33) **Worksite protection** Bollards/cone must be placed at intervals not exceeding 10m. At critical locations the interval distances shall be reduced to 5m or lower (e.g. 1m) depending on the risks.
- 34) Barricades Open trench/pole-hole is to be barricaded on a full time basis by the Contractor.
- 35) **Jobsite Safety Assessment** Contractor to carry out Jobsite Safety Assessment daily, and as and when required, and submit these to FEA on a weekly basis.
- 36) **Credit of surplus material** The contractor shall transport and credit all unused materials to the designated FEA Stores promptly after the completion of each job. Note that the award of new projects may be put on hold until material verification has been completed.
- 37) **Defects Rectification** The contractor shall rectify all defects within seven (7) days as per the contract.



- 38) **Project completion** The contractor shall complete work on time as per the contract.
- 39) **Project progress** If the Contractor fails to proceed with the works with reasonable diligence or suspends the works or refuses to comply with the reasonable direction from FEA by reason of which the works are materially affected and any such default continues for a period of seven (7) days after the issue of written notice, FEA may itself call any other person/company/new contractor to complete the works at the Contractor's risk and expense.
- 40) Insurance The Contractor will be required to possess valid insurance policies as shown below:

Policy type	Value
Workers Compensation	\$250,000
Public Liability	\$500,000
Contractors All Risk	\$500,000

- 41) OHS Compliance To provide/submit evidence of OHS compliance from the Ministry of Labour
- 42) **Personal Protective Equipment** Submit a list of personal protective equipment (PPE) available with the contractor.
- 43) **HSE Requirements** The contractor's bid shall include all requirements from the FEA HSE Contractor Safety Management System. These will be evaluated by the FEA's HSE Unit. Bids with incomplete, unacceptable, or without the HSE requirements will not be considered for award. The Contractor must submit the following with their bid:
 - i) **Contractor HSE Specification** it contains 10 clauses which contains the overall HSE requirements and the contractor needs to agree to this.
 - ii) **Contractor HSE Plan** (Document HSE41C04) The contractor shall fill in each part of the Plan.
 - iii) The Contractor will list down all the plants and equipment to be used in the **Plant & Equipment Register** as well as chemicals in the **Chemical register**.
 - iv) The JSA & Risk Assessment form will require the contractor to identify hazards which may not have been adequately addressed in FEA's existing procedures and outline proposed controls.



D: FEA REQUIREMENT

- FEA Project Supervisor shall obtain Road/footpath opening permits.
- FEA Project Engineer shall obtain clearance from Municipal Council, Telecom Fiji Ltd, Water Supply Department, and Sewerage Department.
- FEA's HSE Unit shall vet Safety Plan submitted by Contractor and approve after queries clarified by Contractor.
- FEA Project Engineer shall ensure that any FEA underground mains on the jobsite is clearly located, marked and identified to the Contractor.
- FEA Project Engineer shall submit to the Project Manager all necessary approval documentation from Municipal Council, Fiji Roads Authority, Telecom Fiji Ltd, Water Supply Department and Sewerage Department. Upon receipt of these approvals, and the approved Safety Plan, the Project Manager shall issue an "Instruction to Commence Work" to the Contractor.
- FEA Project Supervisor and Project Engineer shall carry out regular site inspections to ensure compliance with HSE requirements, and submit Safety Visit Reports of the visit.
- FEA Project Supervisor and Project Engineer shall issue Non-Conformance Report if required, and follow up for verification of implementation of Action Items arising out of the Non-Conformance Report.

E: PAYMENT SCHEDULE

Payment shall be made as per payment schedule:

Phase	Description	Percentage payment
1	Material Transportation to worksite	15%
2	Installation of pole and dressing, stays etc.	50%
4	Conductor Stringing	20%
5	Transformer installation complete	5%
6	Retention	10% to be released after 6 months
		pending zero defects.



Submission of Tender

Two (2) hard copies of the tender bids in sealed envelope shall be deposited in the tender box located at the Supply Chain Office at the FEA Head Office, 2 Marlow Street, Suva, Fiji.

Courier charges for delivery of Tender Document must be paid by the bidders.

This tender closes at 4:00p.m (16.00hrs Fiji time) on Wednesday, 30th November, 2016.

Site visit: 10.00am on Wednesday 23 November 2016 at the FEA's Navutu Depot in Lautoka.

Each tender shall be sealed in an envelope with:

The envelope bearing only the following marking:

Tender- MR 133/2016 – Construction of Overhead Power Line for the Supply to Nadi Land Development at Legalega, Nadi

The Secretary, Tender Committee Fiji Electricity Authority

Supply Chain Office

Private Mail Bag, Suva

It must also indicate the name and address of the tenderer on the reverse of the envelope.

All late tenders, unmarked Envelopes and envelopes without bidder's name and address on the reverse on the envelope will be returned to the Tenderers unopened. (Bids via e-mail or fax will not be considered).

For further information or clarification please contact our Supply Chain Office on phone (+679) 3224360 or (+679) 9991587.